



**27 July 2015**

**Addendum 1  
Transportation Impact  
Emerald Isle , NC**

The following addendum is the result of contractor and owner negotiations and supersede previous information and does hereby become part of the contract documents.

- See Revisions to Architectural Drawings dated 27 July 2015
- See Revisions to Site /Civil Drawings
- Please note that the structural drawings as well as the PME drawings have not been revised to reflect the architectural revisions made. The General Contractor and subcontractors shall be responsible to coordinate these requirements. Some of the major items are as indicated below:
- S1.3 and S1.4: Please note that Stair 3 no longer goes to the roof. Contractor to coordinate structural requirements. See also Architectural Drawings.
- P2.3, P3.3a, P3.3b: The one bedroom unit has been eliminated and will be constructed as an unfinished shell area. Rough in future toilets in area as directed by owner.
- P2.5: Stair 3 no longer goes to the roof level. See Revised Architectural.
- M2.3: Please note that the one bedroom unit will be constructed as an unfinished shell.
- E2.3,E3.3,FA 2.3: Please note that the one bedroom unit will be constructed as an unfinished shell. Provide temporary general purpose lighting in this shell area. Rough in for future electrical panel (verify location)
- E2.4 : Janitor 404 has been eliminated and an exit to the Private Patio area has been added. Coordinate Lighting and switching. Stair 3 no longer goes to the roof level. Adjust lights and switches accordingly.
- E2.1,E2.2: Please note that the glass partitions for offices 103, 104, 105, 106, 107, 203, 204, 205, 206, 208, 209, 210 have been revised to stud and GWB partitions. Please relocate light switches to beside each door opening.
- E3.1, E3.2: Please note that the glass and smart glass partitions have been replaced with metal studs and GWB in offices 103, 104, 105, 106, 107, 203, 204, 205, 206, 208, 209, 210. In the new stud and GWB partitions please add (1) wall receptacle and (1) Data receptacle) in each of these locations.
- FA2.4: Please note that Stair 3 no longer goes to the roof, adjust Fire Alarm Devices accordingly.

**End of Addendum**