



24 May, 2018

Addendum 1

St. Andrew's Episcopal Church
Morehead City, North Carolina

The following addendum shall supersede previous information and does hereby become part of the contract documents.

- For details shown on page S1.2 reference 2/S1.2 and 3/S1.2 please note that the finish of the new wood braces should be stained to match existing wood work.
- All hangers and straps that are added to the repair shall match the finish of the existing metal connections on the existing wood trusses.
- Please note for detail 2/S1.2 the horizontal braces coming together as shown in 5/S2.1 that the existing decorative trim on the bottom of the intersection of the bottom cord of the trusses will need to be removed and re-attached when the braces are applied, please note that you will have to connect through the new steel plate/hangers in these areas.
- Contractor should field verify all existing light fixtures etc. in conflict of new braces and new metal plates. Reinstall in adjacent area that does not interfere with new work. Architect to approve exact location.
- Please note that the base bid is work shown on sheet S1.1. The work on S1.2 will be Add Alternates 1-3 as described in the bidding documents. The owner will choose from one of the Add Alternates 1-3. Please note that one of these alternates must be accepted along with the base bid.

End of Addendum 1